

**STATEMENT OF WORK**  
**Waste Treatment Lagoon (359)**  
**Virginia**

**These deliverables apply to this individual practice. For other planned practice deliverables, refer to those specific Statements of Work.**

## **DESIGN**

---

### **Deliverables:**

1. Design documentation that will demonstrate that the criteria in the NRCS practice standard have been met and are compatible with other planned and applied practices:
  - a. Identify, discuss and document client needs, and recommend method of resolution.
  - b. Practice purpose(s) as identified in the conservation plan.
  - c. List of required permits to be obtained by the client.
  - d. Compliance with NRCS national and state utility safety policy (NEM Part 503-Safety, Subpart A - Engineering Activities Affecting Utilities 503.00 through 503.06). This includes contacting MISS UTILITY (811 or 1-800-552-7001) a minimum of 3 days before beginning construction.
  - e. List of associated practices (conservation practice name and number).
  - f. Practice standard criteria related computations and analyses to develop plans and specifications including but not limited to:
    - i. Geology and Soil Mechanics (NEM Subpart 531a).
    - ii. Storage and Treatment Volume.
    - iii. Maximum Operating Level.
    - iv. Structural, Mechanical and Appurtenances.
    - v. Maximize clean water diversion.
    - vi. Environmental Considerations (e.g. liner failure, location, breaching, air quality).
    - vii. Safety Considerations (NEM Part 503- Safety, Subpart A, 503.06 through 503.12).
2. Provide written plans and specifications, including sketches and drawings, to the client that adequately describe the requirements to install the practice and obtain necessary permits. Develop plans and specifications in accordance with the requirements in the Virginia NRCS Conservation Practice Standard *Waste Treatment Lagoon (Code 359)*.
3. Design Report and Inspection Plan as appropriate (NEM Part 511, Subpart B Documentation, 511.11 and Part 512, Subpart D Quality Assurance Activities, 512.30 through 512.32).
4. Operation and Maintenance Plan
5. Certification that the design meets NRCS standards and specifications and is in compliance with permits (NEM VA505.03, Amendment VA-22).

## **INSTALLATION**

---

### **Deliverables:**

1. Pre-installation conference with client and contractor.
2. Verification that client has obtained required permits.
3. Staking and layout according to plans and specifications, including applicable layout notes.
4. Installation inspection (according to inspection plan, as appropriate).
  - a. Actual materials used.
  - b. Inspection records.
5. Facilitate and implement required design modifications with client and original designer.
6. Advise client/NRCS on compliance issues with all federal, state, tribal, and local laws, regulations and NRCS policies during installation.

**STATEMENT OF WORK  
Waste Treatment Lagoon (359)  
Virginia**

**CHECK OUT**

---

**Deliverables:**

1. As-Built documentation.
  - a. "Red-line" drawings including but not limited to documentation of final construction, changes to initial design, and changes in materials used.
  - b. Extent of practice units applied.
  - c. Final quantities.
2. Certification that the installation meets NRCS standards and specifications and is in compliance with permits (NEM VA505.03, Amendment VA-22).
3. Progress reporting.

**REFERENCES**

---

- VA NRCS Field Office Technical Guide (eFOTG), Section IV, Conservation Practice Standard - *Waste Storage Lagoon (Code 359)*.
- VA NRCS Field Office Technical Guide (eFOTG), Section IV, Operation and Maintenance Plan - *Waste Storage Lagoon (Code 359)*.
- NRCS Agricultural Waste Management Field Handbook (AWMFH).
- NRCS National Engineering Manual (NEM).
- NRCS National Environmental Compliance Handbook.
- NRCS Cultural Resources Procedures Handbook.