

## STATEMENT OF WORK IRRIGATION WATER CONVEYANCE – ALUMINUM TUBING (430aa) WEST VIRGINIA

These deliverables apply to this individual practice. For other planned practice deliverables refer to those specific Statements of Work.

### DESIGN

---

#### Deliverables:

1. Design documentation that will demonstrate that the criteria in NRCS practice standard have been met and are compatible with other planned and applied practices.
  - a. Practice purpose(s) as identified in the conservation plan
  - b. List of required permits to be obtained by the client
  - c. Compliance with NRCS national and state utility safety policy (NEM Part 503-Safety, Subpart A - Engineering Activities Affecting Utilities 503.00 through 503.06)
  - d. Practice standard criteria related computations and analyses to develop plans and specifications including but not limited to:
    - i. Capacity
    - ii. Hydraulics and Appurtenance Design
    - iii. Trench and Backfill Requirements
    - iv. Materials
    - v. Vegetation
2. Written plans and specifications including sketches and drawings shall be provided to the client that adequately describes the requirements to install the practice and obtain necessary permits.
3. Design Report and Inspection Plan as appropriate (NEM Part 511, Subpart B Documentation, 511.11 and Part 512, Subpart D Quality Assurance Activities, 512.30 through 512.32).
4. Operation and Maintenance Plan
5. Certification that the design meets practice standard criteria and comply with applicable laws and regulations (NEM Subpart A, 505.03 (a) (3)).
6. Design modifications during installation as required.

***Note: Design of practice shall be in compliance with practice standard and applicable criteria for the appropriate purpose(s). Practice specification will include the information listed in the "Plans and Specifications" and "Operation and Maintenance" section of the conservation practice standard. The design will document the clients' decisions using narrative and/or jobsheet.***

### INSTALLATION

---

#### Deliverables

1. Pre Installation conference with client and contractor.
2. Verification that client has obtained required permits.
3. Staking and layout according to plans and specifications including applicable layout notes.
4. Installation inspection (according to inspection plan as appropriate).
  - a. Actual materials used (Part 512, Subpart D Quality Assurance Activities, 512.33)
  - b. Inspection records
5. Facilitate and implement required design modifications with client and original designer
6. Advise client/NRCS on compliance issues with all federal, state, tribal, and local laws, regulations and NRCS policies during installation.
7. Certification that the installation process and materials meets design and permit requirements.

### CHECK OUT

---

#### Deliverables

1. As-Built documentation.
  - a. Extent of practice units applied
  - b. Drawings
  - c. Final quantities

**STATEMENT OF WORK**  
**IRRIGATION WATER CONVEYANCE – ALUMINUM TUBING (430aa)**  
**WEST VIRGINIA**

2. Certification that the installation meets NRCS standards and specifications and is in compliance with permits (NEM Subpart A, 505.03 (c) (1)).
3. Progress reporting.
1. Certification that the installation meets NRCS standards and specifications and is in compliance with permits (NEM Subpart A, 505.03 (c) (1)).
2. Progress reporting

**REFERENCES**

---

- Water Conveyance Aluminum Tubing, 430aa
- NRCS National Engineering Manual (NEM).
- NRCS National Environmental Compliance Handbook
- NRCS Cultural Resources Handbook