

STATEMENT OF WORK
Riparian Forest Buffer (391)
Wyoming

These deliverables apply to this individual practice. For other planned practice deliverables refer to those specific Statements of Work.

DESIGN

Deliverables:

1. Design documents that demonstrate criteria in NRCS practice standard have been met and are compatible with planned and applied practices.
 - a. Practice purpose(s) as identified in the conservation plan
 - b. List of required permits to be obtained by the client
 - c. Practice standard criteria-related computations and analyses to develop plans and specifications including but not limited to:
 - i. Determination of buffer zone widths and lengths and adapted species of woody plants to be planted, retained, and/or naturally reestablished in applicable zones
 - ii. Protective measures for planted stock including use exclusion
 - iii. Additional provisions, as required, for reducing excess amounts of pollutants in surface runoff and shallow ground water flow (creation of a zone 2 and a zone 3); providing habitat for aquatic organisms and terrestrial wildlife; and increasing carbon storage in biomass and soils

For guidance see Plant Materials Technical Notice 2, Plant Materials Technical Notice 3, Plant Materials Technical Notice 4, Plant Materials Technical Notice 8, Plant Materials Technical Notice 9
2. Written plans and specifications including sketches and drawings shall be provided to the client that adequately describes the requirements to install the practice and obtain necessary permits.
3. Documentation of needed operation and maintenance.
4. Certification that the design meets practice standard criteria and comply with applicable laws and regulations.
5. Design modifications during installation as required.

INSTALLATION

Deliverables

1. Pre-application conference with client.
2. Verification that client has obtained required permits.
3. Staking and layout according to plans and specifications including applicable layout notes.
4. Application guidance as needed.
5. Facilitate and implement required design modifications with client and original designer.
6. Advise client/NRCS on compliance issues with all federal, state, tribal, and local laws, regulations and NRCS policies during installation.
7. Certification that the application process and materials meet design and permit requirements.

CHECK OUT

Deliverables

1. Records of application.
 - a. Extent of practice units applied
 - b. Width and extent of buffer zones
 - c. Actual plant materials used and protective measures
2. Certification that the application meets NRCS standards and specifications and is in compliance with permits.
3. Progress reporting.

**STATEMENT OF WORK
Riparian Forest Buffer (391)
Wyoming**

REFERENCES

- NRCS Field Office Technical Guide (eFOTG), Section IV:
 - Conservation Practice Standard Riparian Forest Buffer-391 and Riparian Forest Buffer Work Sheet WY-ECS-79
- NRCS Field Office Technical Guide (eFOTG), Section I, Table of Contents:
 - Plant Materials Technical Notice 2-Riparian Forest Buffer Establishment
 - Plant Materials Technical Notice 3-Establishment of Permanent Vegetation
 - Plant Materials Technical Notice 4-Users Guide to Description, Propagation and Establishment of Native Shrubs and Trees for Riparian Areas in the Intermountain West
 - Plant Materials Technical Notice 8-Riparian Forest Buffer Linear Planting Rates
 - Plant Materials Technical Notice 9-Plant Materials for Conservation Buffers
- NRCS Field Office Technical Guide (eFOTG), Section II:
 - Windbreak Suitability Groups by County for each Soil Component
- Conservation Planning Handbook for Wyoming and Colorado
- NRCS National Forestry Handbook (NFH), Part 636.4
- NRCS National Environmental Compliance Handbook
- NRCS Cultural Resources Handbook