

**NATURAL RESOURCES CONSERVATION SERVICE**  
**Wyoming**  
**CONSTRUCTION SPECIFICATIONS**  
**FOR**  
**SURFACE DRAIN, FIELD DITCH**

---

(Owner/Operator)

---

(Project/Title)

**GENERAL**

Installation shall be in accordance with an approved design and plan. Details of construction shown on the drawings but not included herein are considered as a part of this specification. Construction activities shall be in accordance with applicable OSHA regulations.

**FOUNDATION PREPARATION**

The foundation area for all ditches and embankments shall be cleared and stripped of all brush, roots, sod, large rock or other material.

**EXCAVATION**

Ditches shall be excavated to the lines and specified grades as shown on the drawings or as staked in the field. The finished cross-section shall have a smooth surface.

Excess materials shall be disposed in designated spoil disposal areas. All berms and spoil areas shall be smoothed and seeded.

**STRUCTURES**

Structures shall be installed in conjunction with the ditch when shown or listed on the drawings. Construction shall be in accordance with applicable Wyoming Construction Specification 578 or as noted in ADDITION SPECIFICATIONS of this Specification.

**ADDITIONAL SPECIFICATIONS**